REPLACE EXISTING PAVERS WITH 100 THICK CONCRETE FOOTPATH, TOTAL AREA 163sq.m.
TAPER FOOTPATH OUT 300 FROM EXISTING ALIGNMENT, NOM. FROM CH12.0 TO CH82.0.

NOM. AREA OF EXISTING PLOTS, ADJACENT ROCK WALL.

EXISTING POND

EXISTING ROCK WALL.

TIE CONCRETE FOOTPATH INTO EXISTING PATH.

EXISTING CONCRETE FOOTPATH.

TIE CONCRETE FOOTPATH INTO EXISTING KERB RAMP WING.

REMOVE PAVERS AND ADD TOPSOIL OR MULCH.

CH 0
CH 10
CH 20
CH 30
CH 40
CH 50
CH 60
CH 70
CH 80
CH 90
CH 100
CH 110

SW

LEGEND

- EXISTING PATH EDGE
- EXISTING FAMILY PLOTS
- EXISTING TIMBER FENCE
- POND WATER LINE
- EXISTING WATER TAP
- EXISTING RUBBISH BIN
- EXISTING SEATING

	REVISION DESCRIPTION	DATE	CHKD
-			
-			
C2	ISSUED FOR PUBLIC CONSULTATION	12/05	JD
C1	ISSUED FOR CONSTRUCTION	26/02	JD
P1	ISSUED FOR PRELIMINARY CHECK	25/02	JD

SCALE HOR.: 1:200 VERT.: 1:200 — SIZE A3
40mm GRID — DATE
DESIGN J. MORGAN 25/02/26
DRAWN J. MORGAN 25/02/26
CHECK J. AGATYN 25/02/26
FILE NAME 14306.dwg

DESIGN CHECK

APPROVED

BURNIE CITY COUNCIL

FOOTPATH REPLACEMENT PROGRAM

BURNIE LAWN CEMETERY

PROPOSED CONCRETE FOOTPATH

DRAWING NUMBER: 5D14306

SHEET NUMBER 01 of 01